



# केन्द्रीय विद्युत अनुसंधान संस्थान

(भारत सरकार की सोसाइटी, विद्युत मंत्रालय)

क्षेत्रीय परीक्षण प्रयोगशाला

3-ए, इंस्टीटयुशनल एरिया, सेक्टर-62, नोएडा-201309 (उ०प्र०)

**CENTRAL POWER RESEARCH INSTITUTE**

(A Government of India Society, Ministry of Power)

**REGIONAL TESTING LABORATORY**

3-A, Institutional Area, Sector - 62, Noida - 201309 (U.P.)

वेबसाइट / Website : <http://cpri.res.in>

संदर्भ क्रमांक : सीपीआरआई/आरटीएल/एचवी/2024-25/377

दिनांक (Date) : 23.08.2024

सेवा में/To,

M/s. SK Engineers India Private Limited  
Plot No-C21 And 71/2, IID Centre  
Industrial Estate, Khordha, Odisha-752057

विषय (Sub): परीक्षण प्रमाणपत्र (Test Report): CPRINOAHVMISC24T0487

Dt.: 22.08.2024

महोदय / Dear sir,

हमारी प्रयोगशाला में आपके सैंपल पर दिनांक 14.08.2024 और 16.08.2024 तक संचालित परीक्षण के संबंध में निम्नलिखित दस्तावेज संलग्न है।

Please find attached the following documents in respect of the test(s) conducted on your sample on 14.08.2024 & 16.08.2024 at our laboratory.

रिपोर्ट में यदि असंगतियां हो तो इस रिपोर्ट के जारी होने की तारीख से 45 दिन के अंदर लिखित रूप में हमारे ध्यान में लाई जाय ताकि आवश्यक संसोधन किया जा सके और इसके लिए रिपोर्ट की सभी मूल प्रतियां लौटाई जाय। कृपया नोट करें कि इस तारीख के बाद प्राप्त अनुरोधों पर कोई कार्यवाही नहीं की जायेगी।

Any discrepancies in the test report must be brought to our notice in writing within 45 days of the date of issue of this test report for effecting necessary corrections for which all the original copies of the test report must be returned.

Please note that request received beyond this date will not be entertained.

दस्तावेजों की प्राप्ति की पावती भेजे।

Please acknowledge receipt of the documents.

सधन्यवाद, Thanking you,

संलग्न : उपरोक्त

Encl : As above

भवदीय (Yours sincerely)

ईकाई- प्रमुख  
Unit-Head

# TEST REPORT



**CENTRAL POWER RESEARCH INSTITUTE**

**(A Govt. of India Society)**

**Regional Testing Laboratory**

**3A, Institutional Area, Sector - 62**

**Noida - 201 309**

# CENTRAL POWER RESEARCH INSTITUTE

## TEST REPORT



# CPRI

Date: 22 August 2024

**Test Report Number** : CPRINOAHVMISC24T0487

**Name and Address of the Customer** : M/s. SK Engineers India Private Limited  
Plot No-C21 And 71/2, IID Centre  
Indusrial Estate Khordha, Odisha-752057

**Name and Address of the Manufacturer** : M/s. SK Engineers India Private Limited  
Plot No-C21 And 71/2, IID Centre  
Indusrial Estate Khordha, Odisha-752057

**Particulars of sample tested** : 415 V, 4000 A, 3 Phase, LT Panel

**Type** : Main Distribution Panel

**Description of test sample** : Refer Sheet 2 of 6

**Serial Number** : SKEIPL/02/07/24/2372

**Number of samples tested** : One

**Date(s) of Test(s)** : 14 & 16 August 2024

**CPRI Sample code Number(s)** : NOAHVMISC24S0472

**Particulars of tests conducted** : Refer sheet 3 of 6

**Test in accordance with Standard/Specification** : As per customer requirement & procedure followed as per IS/IEC 61439-1: 2020 & IS/IEC 61439-2: 2020

**Sampling Plan** : Nil

**Customer's Requirement** : Maximum temperature rise on busbar & busbar joints shall be  $\leq 70K$

**Deviations if any** : Nil

**Name of the witnessing persons**

**Customers representative** : Mr. Tapas Das

**Other than customer's representatives** : Nil

**Test subcontracted with address of the laboratory** : Nil

**Documents constituting this report (in words)**

**Number of Sheets** : Six

**Number of Oscillogram(s)** : Nil

**Number of Graph(s)** : Nil

**Number of Photograph(s)** : One

**Number of Test Circuit Diagram(s)** : Nil

**Number of Drawing(s)** : Three

(Gangeshwar Singh)  
Test Engineer



(M.K. Jaiswal)  
Head of Division  
Reviewed and Authorized by

# CENTRAL POWER RESEARCH INSTITUTE

## TEST REPORT



# CPRI

Test Report Number: CPRINOAHVMISC24T0487

Date: 22 August 2024

### DESCRIPTION OF SAMPLE TESTED

(As assigned by the manufacturer)

Sample	: LT Panel
Rated voltage (Volts)	: 415
Rated current (Amps)	: 4000
Frequency (Hz)	: 50
Insulation level	: 690 V
No. of Phase	: 3 PH+N
Rated Short Time Current	: 70 kA <sub>rms</sub> for one second with initial peak of 154 kA <sub>peak</sub>
Pollution Degree	: 3
Material Group	: IIIa

  
(Gangeshwar Singh)  
Test Engineer

TEST REPORT



**CPRI**

Test Report Number: CPRINOAHVMISC24T0487

Date: 22 August 2024

**SUMMARY OF TESTS CONDUCTED**

- |                            |   |  |
|----------------------------|---|--|
| 1. Tests conducted         | : | 1. Verification of Temperature Rise<br>2. Verification of Di-electric Property<br>3. Verification of Clearance & Creepage Distance |
| 2. Rating for which tested | : | 1. 4000 Amps, 50Hz<br>2. 1.89 kV <sub>rms</sub><br>3. As per customer requirement  |
| 3. Schedule of tests       |   |  |

Tests Conducted	Clause Numbers	Sheet
Verification of Temperature Rise	As per customer requirement	4 of 6
Verification of Di-electric Property	As per customer requirement	5 of 6
Verification of Clearance & Creepage Distance	As per customer requirement	5 of 6

- |                                 |   |                         |
|---------------------------------|---|-------------------------|
| 4. Oscillogram Numbers          | : | Nil                     |
| 5. Graph Numbers                | : | Nil                     |
| 6. Photograph Numbers           | : | CPRINOAHVMISC24T0487P01 |
| 7. Test Circuit Diagram Numbers | : | Nil                     |
| 8. Drawing Numbers              | : | As given below          |

**Drawing Numbers**

The manufacturer has guaranteed that the sample submitted for the test(s) has been manufactured in accordance with the following drawings

Sl. No.	Drawing Number	Sheet Number	Revision Number
1	SKEIPL/HRT/NOIDA/01	1 of 3	00
2	SKEIPL/HRT/NOIDA/01	2 of 3	00
3	SKEIPL/HRT/NOIDA/01	3 of 3	00

It is verified that these drawings adequately represent the sample tested. Verification of these drawings by CPRI is limited to dimensional check only wherever possible.

  
(Gangeshwar Singh)  
Test Engineer

# CENTRAL POWER RESEARCH INSTITUTE

## TEST REPORT



Test Report Number: CPRINOAHVMISC24T0487

**CPRI**  
Date: 22 August 2024

### TEST RESULTS

**1). Test conducted:** Verification of Temperature Rise

Date of test : 14.08.2024  
Starting time (hrs.) : 11:00  
Shut down time (hrs.) : 15:00  
Test current (A) : 4000  
Size of the conductor used for temporary connection : Aluminium busbar size 150 x 10 sqmm x 4 nos./phase  
Frequency (Hz) : 50  
Phase : 3 PH+N  
Avg. ambient temperature at shut down : 33.2 °C  
Arrangement of thermocouple locations: As per drawing no: SKEIPL/HRT/NOIDA/01 Sheet: 2 of 3 Rev.: 00

Thermocouples		Maximum Temperature (°C)	Temperature Rise (K)
Locations	Numbers		
Incoming Terminal – R1	T01	65.0	31.8
Incoming Terminal – Y1	T02	71.6	38.4
Incoming Terminal – B1	T03	67.4	34.2
Incoming Terminal – R2	T04	71.1	37.9
Incoming Terminal – Y2	T05	73.8	40.6
Incoming Terminal – B2	T06	63.3	30.1
HBB Joint – R	T07	66.6	33.4
HBB Joint – Y	T08	73.7	40.5
HBB Joint – B	T09	69.0	35.8
VBB Joint – R1	T10	59.0	25.8
VBB Joint – Y1	T11	70.0	36.8
VBB Joint – B1	T12	68.1	34.9
VBB Joint – R2	T13	61.7	28.5
VBB Joint – Y2	T14	59.8	26.6
VBB Joint – B2	T15	57.1	23.9
Outgoing Terminal – R1	T16	57.9	24.7
Outgoing Terminal – Y1	T17	60.2	27.0
Outgoing Terminal – B1	T18	60.2	27.0
Outgoing Terminal – R2	T19	61.7	28.5
Outgoing Terminal – Y2	T20	47.4	14.2
Outgoing Terminal – B2	T21	53.5	20.3
Enclosure Top	T22	41.9	8.7
Enclosure Side	T23	40.8	7.6

**Observation:** The maximum temperature rise obtained was within the limits as per the requirements of the customer. After temperature rise test, sample subjected to the HV test to check the effect of temperature rise on adjacent parts of sample. The sample withstood 1.89 kV<sub>rms</sub> for 1 min.

  
(Gangeshwar Singh)  
Test Engineer

# CENTRAL POWER RESEARCH INSTITUTE

## TEST REPORT



# CPRI

Test Report Number: CPRINOAHVMISC24T0487

Date: 22 August 2024

### TEST RESULTS

#### 2. Test conducted: Verification of Dielectric Properties

##### Test Details:

Sl. No.	Voltage applied to	Connected to earth	Voltage applied $kV_{rms}$	Remarks
1	R	Y,B,N & Frame	1.89	Withstood for 60 sec
2	Y	R,B,N & Frame	1.89	Withstood for 60 sec
3	B	R,Y,N & Frame	1.89	Withstood for 60 sec
4	N	R,Y,B & Frame	1.89	Withstood for 60 sec
5	R,Y,B & N	Frame	1.89	Withstood for 60 sec

#### 3. Test conducted: Verification of Clearance & Creepage Distance

Clearance & Creepage Distances were measured as per standard and the value are found for clearance was 19.6 mm and for creepage distance was 22.3 mm which are within the limits as specified in standard for pollution degree-3 and material group-IIIa.

**Conclusion:** The sample tested complies with the requirements of the customer for the tests conducted.

  
(Gangeshwar Singh)  
Test Engineer

# CENTRAL POWER RESEARCH INSTITUTE

## TEST REPORT



# CPRI

Test Report Number: CPRINOAHVMISC24T0487

Date: 22 August 2024

### NOTE

- a) CPRI is responsible for the test results relate only to the sample(s) tested.
- b) Publication or reproduction of this Test Report /Test Certificate in any form other than by complete set of the whole Test Report /Test Certificate and in the language written is not permitted without the written consent of CPRI.
- c) Any Corrections/erasure invalidates the Test Report/Test Certificate
- d) Any anomaly/discrepancy in the Test Report / Test Certificate should be brought to the notice of CPRI within 45 days from the date of issue.

  
(Gangeshwar Singh)  
Test Engineer

-----End of Test Report-----

# CENTRAL POWER RESEARCH INSTITUTE

## TEST REPORT



# CPRI


Test Report Number: CPRINOAHVMISC24T0487

Date: 22 August 2024



Photograph Number: CPRINOAHVMISC24T0487P01

  
(Gangeshwar Singh)  
Test Engineer



**NOTES:-**

1. PAINT SHADE ENCL:- SIEMENS GREY (RAL 7032).
2. SHEET ENCL. :- 2MM THICK CRCA SHEET.
3. CABLE ENTRY :- TOP AND BOTTOM


**परिक्षण रिपोर्ट सं./Test Report No. CPRI/NOAHVMISC24TO487**  
दिनांक/Date.....22 August 2024

**परीक्षण अभियंता**  
आरटीएल, सीपीआरआई नोएडा  
**TEST ENGINEER**  
RTL, CPRI, NOIDA

**Tolerance - 3 %.**  
**All Dimensions in mm**

*(Handwritten Signature)*

<b>MANUFACTURED BY:</b>  <b>Engineers India Pvt Ltd</b> <small>An ISO 9001:2015 Certified Company</small> Plot no - C/21 and 71/2, IID Center, Industrial Estate, Khorda, Odisha-752057.	<b>TEST DETAILS</b>		<b>RATED VOLTAGE : 415 VAC.</b>		SCALE	SHEET	DATE	DRAWN	Mr. PRAKASH
	<b>TEMPERATURE RISE TESTING</b> for LT PANEL 4000A		<b>CURRENT : 4000 A</b>		NTS	1 OF 3	12-08-2024	APPROVED	Mr. Tapas. Das
				<b>TYPE : MAIN DISTRIBUTION PANEL</b>		REV		SR. NO	SKEIPL/02/07/24/2372
				<b>DESIGNATION : PCC CUM MCC CONTROL CENTRE</b>		00.		DRG.NO	SKEIPL/HR7/NOIDA/01.



THERMOCOUPLES	
T1	- R1 INCOMING
T2	- Y1 INCOMING
T3	- B1 INCOMING
T4	- R2 INCOMING
T5	- Y2 INCOMING
T6	- B2 INCOMING
T7	- R HBB JOINT
T8	- Y HBB JOINT
T9	- B HBB JOINT
T10	- R1 VBB JOINT
T11	- Y1 VBB JOINT
T12	- B1 VBB JOINT
T13	- R2 VBB JOINT
T14	- Y2 VBB JOINT
T15	- B2 VBB JOINT
T16	- R1 OUTGOING
T17	- Y1 OUTGOING
T18	- B1 OUTGOING
T19	- R2 OUTGOING
T20	- Y2 OUTGOING
T21	- B2 OUTGOING
T22	- BODY 1
T23	- BODY 2

GEN TOLERANCE  $\pm 2\%$   
ALL DIMENSIONS ARE IN MM


यह चित्र सीपीआरआई से संबंधित है।  
This drawing pertains to CPRI

परीक्षण रिपोर्ट सं./Test Report No. **CPRI.N.O.AHVMISSC24 TO 497**  
दिनांक/Date: **22 August 2024**

INCOMING FOR TEST PURPOSES

*(Signature)*  
परीक्षण अभियंता  
अनुराग, सीपीआरआई नोएडा  
**TEST ENGINEER**  
RTL, CPRI, NOIDA

MANUFACTURED BY: <b>Engineers India Pvt Ltd</b> <small>Plot no - C/21 and 71/2, IID Center, Industrial Estate, Khorda, Odisha-752057.</small>	TEST DETAILS		RATED VOLTAGE : 415 VAC.		SCALE	SHEET	DATE	DRAWN	Mr. Prakash
	TEMPERATURE RISE TESTING for LT PANEL 4000A		CURRENT : 4000 A		NTS	2 OF 3	12-08-2024	APPROVED	Mr. Tapas Das
		DESIGNATION : PCC CUM MCC CONTROL CENTRE		TYPE : MAIN DISTRIBUTION PANEL		REV		SR. NO	SKEIPL/02/07/24/2372
				NTS		REV		DRG.NO	SKEIPL/HRT/NOIDA/01.



SUPPORT FOR PH & N  
 MATERIAL : POLYIMIDE  
 TOLERANCE = ±1MM  
 MAKE : POWERMAT

सीपीआरआई द्वारा इस चित्र का सत्यापन  
 जहाँ भी संभव हो, यह केवल आयामी  
 जांच तक ही सीमित है।  
 VERIFICATION OF THIS DRAWING  
 BY CPRI IS LIMITED TO  
 DIMENSIONAL CHECK ONLY, WHEREVER POSSIBLE

यह चित्र सीपीआरआई से संबंधित है।  
 This drawing pertains to CPRI

परीक्षण रिपोर्ट सं./Test Report No...CPRI/NO.24/HV/MISC/24/10 487

दिनांक/Date.....22.....August.....2024

*Prakash*  
 परीक्षण अभियंता  
 स्टार्टीएल, सीपीआरआई नोएडा  
 TEST ENGINEER  
 RTL, CPRI, NOIDA

<b>MANUFACTURED BY:</b> <b>Engineers India Pvt Ltd</b> <small>INCORPORATED IN INDIA</small> Plot no - C/21 and 71/2, IID Center, Industrial Estate, Khorda, Odisha-752057.	<b>TEST DETAILS</b> TEMPERATURE RISE TESTING for LT PANEL 4000A		RATED VOLTAGE : 415 VAC. CURRENT : 4000 A TYPE : MAIN DISTRIBUTION PANEL DESIGNATION : PCC CUM MCC CONTROL CENTRE		SCALE NTS 	SHEET 3 OF 3	DATE 12-08-2024	DRAWN APPROVED	Mr. Prakash Mr. Tapas. Das
					REV 00.	SR. NO DRG.NO	SKEIPL/02/07/24/2372 SKEIPL/HRT/NOIDA/01.		